

Technical Note

Metallosis: A diagnosis not only in patients with metal-on-metal prostheses

Catarina A. Oliveira^{a,*}, Isabel S. Candelária^a, Pedro B. Oliveira^a, Antonio Figueiredo^b,
Filipe Caseiro-Alves^a

^a Medical Imaging Department and Faculty of Medicine, University Hospital of Coimbra, Portugal

^b Orthopedics Department, University Hospital of Coimbra, Portugal

Received 15 November 2014; accepted 18 November 2014

Available online 28 November 2014

Abstract

Although the real actual incidence of metallosis is unknown, it is described as a rare diagnosis with a 5% estimated incidence in the hip prosthetic replacements. The adoption of non-metallic articular prosthetic devices, made of polyethylene and ceramic, is the main reason to the diminishing number of reported cases. We present a case of metallosis with a clinical systemic presentation in a patient with a non-metallic hip prosthesis, which occurred due to a fracture of the acetabular liner component, leading to abnormal metal–metal contact. The metallic debris leads to a massive local and systemic release of cytokines. Revision is necessary whenever osteolysis and loosening of the prosthesis occur. Imaging evaluation, especially CT, has a central role in diagnosis and planning the surgical treatment.

© 2014 Published by Elsevier Ltd. This is an open access article under the CC BY-NC-ND license (<http://creativecommons.org/licenses/by-nc-nd/4.0/>).

Keywords: Metallosis; Hip prosthesis; Computed tomography

1. Introduction

Arthroplasty complications include many pathological entities. The most common are infection, peri-prosthetic fractures, dislocations, osteolysis and heterotopic ossification [1,2].

Metallosis is a rare, potentially fatal complication after arthroplasty, but is generally associated with metal-on-metal prosthetic devices, but it has also been described in non-metallic prostheses [3]. It is defined as aseptic fibrosis, local necrosis, or loosening of a device secondary to metal corrosion and release of wear debris [4,5]. It occurs due to metallic erosion and release of metallic debris products, which induce massive local cytokines liberation from inflammatory cells [3,6]. The systemic absorption of metallic particles can cause several clinical presentations depending on the predominant affected system. We present a case of metallosis, with a hemolytic anemia presentation in a patient with a non-metallic prosthesis, which occurred due to

fracture of the non-metallic component, leading to metal-metal contact. Exuberant radiological findings are described and their importance in surgical treatment planning is highlighted.

2. Case report

A 55-year-old male presented to the emergence department complaining of right hip pain, malaise, intermittent fever and “red urine”. He also referred to weight loss. On physical examination he had jaundice and a right hip mass with fluctuation, but no significant inflammatory signs. Laboratorial findings revealed a hemolytic anemia, with elevated bilirubin and LDH and a positive Combs test, indicating an immunological mediated process. Hyperglycemia was also noted. The patient had a clinical history of total right hip arthroplasty four years previously with cementless modular ceramic–ceramic articulation prosthesis; the femoral and acetabular components were made of titanium alloy (titanium, aluminum and vanadium). A year later, he had a left total hip arthroplasty with a cementless prosthesis, with metal-polyethylene articulation and femoral stem and acetabular components made of titanium alloy. He had a recent (a year ago) history of surgical review of the right hip

* Corresponding author at: Serviço de Imagem Médica, Hospitais da Universidade de Coimbra, Praceta Prof. Mota Pinto, 3000-075 Coimbra, Portugal.
Tel.: +351 919838393.

E-mail address: kat.catarina@gmail.com (C.A. Oliveira).




Fig. 1. A 55-years-old man with metallosis. Plain film of pelvis, revealing two round high-density images, one denser projected on the right iliac bone and the other above the right femoral neck (arrows). High density fragments adjacent to the inferior acetabular border were also noted (arrowhead). There is also an eccentric position of the femoral head in the acetabular dome (non equal distance between the femoral head margin and the acetabular border – trace lines).

prosthesis due to a fracture of ceramic acetabular liner and its replacement with a polyethylene one.

In the emergency department he performed a pelvic plain film that revealed a subtle misalignment, with eccentric location of the right femoral head, and two rounded high-density images: one denser image projected on the right iliac bone and the other above the femoral neck (Fig. 1).

A non-imaging guide puncture to the periarticular right hip mass was performed in the emergency department with drainage of abundant black liquid (Fig. 2) indicating metallosis diagnosis. The black liquid color is due to the metallic components debris and basic chemistry is usually not necessary for the diagnosis.

Hours after the procedure, the patient showed improvement of all clinical signs (fever, malaise) and analytical hyperglycemia



Fig. 2. A 55-years-old man with metallosis. Photograph of the black fluid drained after the right hip fluctuating mass puncture.

values return to normal values. He was then discharged home, with referred appointment control in a week. Four days later, he returned to the emergency department, complaining of malaise. Analytical control in the emergency department revealed worsening of anemia and hyperglycemia levels. A CT scan was then performed. CT findings revealed a large elongated collection of high density content, extending from the articular space in to the pelvis along the right psoas muscle (Fig. 3), in relation with metallic components debris.

To avoid continuous absorption of the metallic particles, urgent surgical procedure to provide collection drainage was necessary. Due to the patient's systemic clinical impairment, a temporary pulsatile cleaning system was installed. An incision was made in the right lateral the hip and a draining cleaning system provided the liquid outlet. High-dose corticosteroid therapy and blood transfusion were performed, and after rising in red blood cells count, the patient underwent a second revision of the right hip prosthetic device. Intra-operative findings confirmed the extensive metallosis; metal impregnation of the replaced polyethylene liner component, as well as wear of the acetabular metal dome. To allow direct access to the pelvic collection along the right psoas muscle, a trans-acetabular perforation was made and abundant black liquid was drained (Fig. 4). After surgery the patient made a good recovery, with improvement of all clinical parameters and analytical values.

3. Discussion

Radiological evaluation of a prosthetic implant should always be preceded by the knowledge of the type of implant. Each of them has a different imaging appearance and different associated risk complications. Complications manifesting as dense areas are rare and have a narrow differential diagnosis. Most frequent are heterotopic ossification and cement extravasation [1]. Cement extravasation was excluded in this case, because this was a cementless prosthesis.

Heterotopic ossification occurs when primitive mesenchymal cells in the surrounding soft tissues are transformed into osteoblastic cells and form mature bone. It typically occurs around the femoral neck and adjacent to the greater trochanter in 15–50% of patients. Many patients with low-grade heterotopic ossification are asymptomatic. Articular stiffness and pain are the main clinical complaints [1,2].

Metallosis was first described in association with setting of the fixation of fractures with metal implants [7]. The adoption of articular components made of other materials such as polyethylene or ceramic has dramatically reduced its incidence in patients with articular prostheses, and nowadays it is a rare complication (5.3% of total hip arthroplasty complications) [1,2,8]. Although less frequent, even with polyethylene or ceramic articular components metallosis can occur if there is abnormal metal-on-metal contact due to wear or fracture of the articular component [6,9]. Wear-through and dislodgement of the acetabular liner may be influenced by several factors, including use of thin polyethylene insert and the method of sterilization treatment of polyethylene liners [9]. Chronic abrasion between the metal components induces the release and infiltration of metallic

Download English Version:

<https://daneshyari.com/en/article/4229697>

Download Persian Version:

<https://daneshyari.com/article/4229697>

[Daneshyari.com](https://daneshyari.com)