



Available online at www.sciencedirect.com



Procedia

Energy Procedia 105 (2017) 335 – 342

### The 8<sup>th</sup> International Conference on Applied Energy – ICAE2016

## Termination control temperature study for an air source heat pump unit during its reverse cycle defrosting

SONG Mengjie<sup>a,\*</sup>, WANG Xuanjie<sup>b</sup>, LIAO Liyuan<sup>a</sup>, DENG Shiming<sup>c</sup>

<sup>a</sup> Department of Energy Engineering, School of Materials and Energy, Guangdong University of Technolog, Guangzhou, China
<sup>b</sup>Department of Mechanical and Aerospace Engineering, The Hong Kong University of Science and Technology, Kowloon, Hong Kong SAR

<sup>c</sup> Department of Building Services Engineering, The Hong Kong Polytechnic University, Kowloon, Hong Kong SAR

#### Abstract

For an air source heat pump (ASHP) unit with a vertically installed multi-circuit outdoor coil, a reverse cycle defrosting (RCD) operation is always terminated when the tube surface temperature at the exit of the lowest circuit reaches a pre-set value. It is obviously that when the pre-set temperature is higher, the defrosting duration would be prolonged. Not only more energy would be consumed on heating cold ambient air, but also the occupants' thermal comfort adversely affected. However, if the pre-set temperature is lower, more residual water would be left on the downside surface of fin in an outdoor coil, which degrades the system performance during the next frosting/defrosting cycle. In order to find a suitable DTT or its range, in this paper, an experimental investigation on RCD operation for an ASHP unit with a multi-circuit outdoor coil was conducted and reported. As concluded, DTT is suitable at the range of 20-25 °C, around 22 °C.

© 2017 The Authors. Published by Elsevier Ltd. This is an open access article under the CC BY-NC-ND license (http://creativecommons.org/licenses/by-nc-nd/4.0/).

Peer-review under responsibility of the scientific committee of the 8th International Conference on Applied Energy.

Keywords: Air source heat pump; Multi-circuit outdoor coil; Reverse cycle defrosting; Defrosting termination temperature; Experimental study

#### **1** Introduction

Air source heat pump (ASHP) units have been widely used as cooling and heating sources for heating, ventilation and air conditioning installations over the recent decades in many parts of the world because of their advantages such as energy saving, environmental protection and flexibility. However, when an ASHP unit works in heating mode at high humidity and low temperature environment in winter, it is difficult to avoid frost formation and accumulation on its surface of outdoor coil. The frost layer degrades

1876-6102 © 2017 The Authors. Published by Elsevier Ltd. This is an open access article under the CC BY-NC-ND license (http://creativecommons.org/licenses/by-nc-nd/4.0/).

<sup>\*</sup> Corresponding author. Tel./fax: +86 20 39322581

E-mail address: Mengjie.Song@gmail.com.

system heating/frosting performance and even results in an unexpected shutdown of the ASHP unit. Therefore, periodic defrosting becomes necessary [1].

Currently, there are many defrosting methods, such as 1) compressor shut-down defrosting [2], 2) electric heating defrosting [3,4], 3) hot water spray defrosting [5], 4) hot gas by-pass defrosting [6,7], 5) compressed air blowing defrosting [8,9], 6) ultrasonic vibration defrosting [10,11], etc. However, among these used methods, the most widely used standard defrosting method is reverse cycle defrosting (RCD). When a space heating ASHP unit is operated at a RCD mode, its outdoor coil acts as a condenser and its indoor coil acts as an evaporator [12]. It should be noted that for defrosting on ASHP unit, a complete defrosting process covers both melting frost and drying coil surface. For an outdoor coil used in an ASHP unit, on its refrigerant side, multi-circuit structures are commonly used for minimizing refrigerant pressure loss and enhancing heat transfer efficiency. To save more floor space, a multi-circuit outdoor is always vertically installed. Authors have carried out series experimental and numerical studies to improve the RCD performance of an ASHP unit with a multi-circuit outdoor coil, by eliminating the negative effects of melted frost [12-14], improving the frosting evenness values [15-17], optimizing the refrigerant distribution [18,19], and adjusting the installation style of outdoor coil [20,21], etc.

For an ASHP unit with a vertically installed multi-circuit outdoor coil, a RCD operation is always terminated when the tube surface temperature at exit of the lowest circuit reaches a pre-set value. It is obviously that when the pre-set temperature is higher, the defrosting duration would be prolonged. Not only more energy would be consumed on heating cold ambient air, but also the occupants' thermal comfort adversely affected [22]. Since the ambient air temperature is always at the lowest value at night, sleep thermal comfort problem due to the degraded performance of air conditioning system attract scholar's attentions [23-25]. On the contrary, if the pre-set temperature is lower, more residual water would be left on the surface of outdoor coil, which degrades the system performance during the next frosting/defrosting cycle [26]. In the open literatures, a suitable pre-set temperature, working as defrosting termination temperature (DTT) of a RCD operation, was not fixed. For example, used values consist of 10 °C [27], 12 °C [28], 15 °C [29], 18 °C [30], 20 °C [31], 24 °C [12-21], 26.7 °C [32], and 35 °C [33], etc. Consequently, in order to find a suitable DTT or its range, in this paper, an experimental investigation on RCD operation for an ASHP unit with a multi-circuit outdoor coil was conducted. This study makes contributions on the method to find a suitable DTT for RCD of ASHP units.

#### **2** Experimentation

#### 2.1. Experimental ASHP unit

An experimental ASHP unit was specifically established for carrying out the experimental work reported in this paper. The experimental ASHP unit was installed in an existing environmental chamber having a simulated indoor heated space and a simulated outdoor frosting space. Fig. 1 shows the schematics of the ASHP unit installed in the environmental chamber. The outdoor coil was specially designed and made for this study, as shown in Fig. 2.

#### 2.2. Experimental procedures and conditions

Relative detailed information about the equipment is shown in References [12-14], including experimental procedures and conditions. Specially, in this study, only one experimental case was carried

Download English Version:

# https://daneshyari.com/en/article/5446275

Download Persian Version:

https://daneshyari.com/article/5446275

Daneshyari.com