

Accepted Manuscript

Experimental investigation of the effect of defects in Automated Fibre Placement produced composite laminates

Wilhelm Woigk, Stephen R. Hallett, Mike I. Jones, Moritz Kuhtz, Andreas Hornig, Maik Gude

PII: S0263-8223(17)33994-6

DOI: <https://doi.org/10.1016/j.compstruct.2018.06.078>

Reference: COST 9872

To appear in: *Composite Structures*



Please cite this article as: Woigk, W., Hallett, S.R., Jones, M.I., Kuhtz, M., Hornig, A., Gude, M., Experimental investigation of the effect of defects in Automated Fibre Placement produced composite laminates, *Composite Structures* (2018), doi: <https://doi.org/10.1016/j.compstruct.2018.06.078>

This is a PDF file of an unedited manuscript that has been accepted for publication. As a service to our customers we are providing this early version of the manuscript. The manuscript will undergo copyediting, typesetting, and review of the resulting proof before it is published in its final form. Please note that during the production process errors may be discovered which could affect the content, and all legal disclaimers that apply to the journal pertain.

Experimental investigation of the effect of defects in Automated Fibre Placement produced composite laminates

Wilhelm Woigk^{a,b}, Stephen R. Hallett^a, Mike I. Jones^a, Moritz Kuhtz^b, Andreas Hornig^b, Maik Gude^b

^a*Advanced Composites Collaboration for Innovation & Science (ACCIS), University of Bristol, University Walk, Bristol BS8 1TR, UK*

^b*Technische Universität Dresden, Institute of Lightweight Engineering and Polymer Technology (ILK), Holbeinstr. 3, 01307 Dresden, Germany*

Abstract

Automated composite manufacturing processes such as Automated Tape Laying (ATL) and Automated Fibre Placement (AFP) are effective methods to produce high quality, lightweight parts. Typically, preimpregnated fibres or tapes are laid side-by-side onto a tooling surface to generate the composite preform. Although these two main technologies are widely used to produce large composite components, inconsistencies such as overlapping tapes or gaps between adjacent tapes may occur during the manufacturing. Within this study, the effect of gaps and overlaps, so-called defects, has been investigated experimentally. Tensile and compressive testing has been carried out on specimens with a quasi-isotropic, symmetric layup into which artificial defects in various defined formations were introduced. Of particular interest were the strength knockdown factors and changes in the failure mode.

Keywords: A. Automated fibre placement, B. Defects, C. Fibre misalignment, D. Delamination

1. Introduction

Conventional hand lay-up techniques are strongly confined by the requirement of a manual operator during the manufacturing process. Furthermore, the size of the structure is limited by the worker's reach. In terms of these two aspects, it is obvious that the production of even small composite parts is time-consuming and becomes more uneconomical for greater production numbers. Thus automation is required in most industrial fields to increase the productivity as well as the structures' size [1].

In the area of composite manufacturing two main technologies have been established: Automated Fibre Placement (AFP) and Automated Tape Laying (ATL). These technologies are being employed today to manufacture advanced composite laminates from unidirectional preregs. Both techniques are fairly similar to each other. ATL is able to place wide unidirectional prepreg tapes onto a tooling surface with automatic removal of the ply backing. AFP, in contrast, uses a band of narrow strips or tows of prepreg material. These strips are aligned in the layup head and can be cut individually if desired. Finally, the strips are laid down adjacent to each other [2]. By using one of these techniques large composite parts can be produced.

Download English Version:

<https://daneshyari.com/en/article/6703441>

Download Persian Version:

<https://daneshyari.com/article/6703441>

[Daneshyari.com](https://daneshyari.com)